

**Metric School In Canada**  
Field Report - Totals Only

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes	
T	AIR	CMU-AIR	Air Deduction For CMU	56 m <sup>2</sup>	56.240 m <sup>2</sup>	0.0 m <sup>2</sup> /Day	
	ANC	DRILLEPD	Drill & Epoxy Rebar Dowe	18 Each	18.000 Ea	75.0 Each/Day	
	ANC	FEROTIECM	Fero Tie @ CMU Backup	5,022 Each	5,021.586 Ea	300.0 Each/Day	
	ANC	FEROTIEST	Fero Tie @ Stud Backup	499 Each	499.343 Ea	300.0 Each/Day	
	ANC	REBARPO8	Rebar Positioner 8" CMU	210 Each	210.000 Ea	0.0 Each/Day	
	ANC	TOPWPL	Top Of Wall Plate At Beam	10,932 Each	10,932.000 Ea	75.0 Each/Day	
	BRI	M	Modular Brick Prem+	49,526 Pieces	1,132.819 m <sup>2</sup>	500.0 Pieces/Day	
	BRI	MHSOLID	Modular Half Solid Prem+	1,401 Pieces	16.022 m <sup>2</sup>	500.0 Pieces/Day	
	BRI	MP	Modular Brick Pier Prem+	1,763 Pieces	40.320 m <sup>2</sup>	500.0 Pieces/Day	
	BRI	MS	Modular Brick Soldier	11,015 Pieces	146.937 m <sup>2</sup>	300.0 Pieces/Day	
	BRI	MSOLID	Modular Brick Solid Prem+	1,450 Pieces	33.166 m <sup>2</sup>	500.0 Pieces/Day	
	CMU	10MM	10 mm Metric Hollow Block	10,328 Pieces	826.278 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MM2BNP	10 mm BN Each End Pier	420 Pieces	33.600 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMBN	10 mm Metric BN	3,285 Pieces	262.800 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMBNP	10 mm Metric BN @ Pier	1,646 Pieces	131.680 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMDBN	10 mm Metric DBN	40 Pieces	3.200 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMH	10 mm Metric Half Block	9 Pieces	0.360 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMHBNP	10 mm Metric Half BN Pier	155 Pieces	6.200 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMHDBN	10 mm Metric Half DBN	35 Piece	1.400 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMHP	10 mm Metric Half Pier	14 Piece	0.560 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	10MMP	10 mm Metric Block @ Pier	4,528 Pieces	362.220 m <sup>2</sup>	140.0 Pieces/Day	
	CMU	15MM	15 mm Metric Hollow Block	430 Pieces	34.420 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	15MMBN	15 mm Metric Block BN	60 Pieces	4.800 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	15MMH	15 mm Metric Half Block	24 Piece	0.960 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	15MMHBN	15 mm Metric Half Blk. BN	54 Pieces	2.160 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	15MMKO	15 mm Metric K.O.	18 Piece	1.460 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MM	20 mm Metric Hollow Block	143,104 Pieces	11,448.352 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MM2BNP	20 mm BN Each End Pier	1,435 Pieces	114.800 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMBB	20 mm Metric B.B.	1,988 Pieces	159.020 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMBBE	20 mm Metric B.B. Elevato	24 Pieces	1.950 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMBN	20 mm Metric BN	3,141 Pieces	251.275 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMBNP	20 mm Metric BN Pier	251 Pieces	20.080 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMBNSO	20 mm Metric BN Soldier	2,608 Pieces	208.640 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMDBN	20 mm Metric DBN	474 Pieces	37.920 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MME	20 mm Metric At Elevator	2,235 Pieces	178.780 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMH	20 mm Metric Half Block	8,708 Pieces	348.321 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	20MMHBN	20 mm Half Block BN	2,242 Pieces	89.669 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	20MMHBNP	20 mm Half Block BN Pier	1,700 Pieces	68.000 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	20MMHDBN	20 mm Half Block DBN	439 Pieces	17.574 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	20MMHE	20 mm Half Block Elevator	54 Pieces	2.160 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	20MMHH	20 mm Metric Halfhigh	2,023 Pieces	80.925 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMHP	20 mm Metric Half Block P	676 Pieces	27.040 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	20MMKO	20 mm Metric K.O.	16,808 Pieces	1,344.669 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMKOE	20 mm Metric K.O. Elevato	245 Pieces	19.600 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	20MMP	20 mm Metric Block Pier	91 Pieces	7.240 m <sup>2</sup>	135.0 Pieces/Day	
	CMU	25MM	25 mm Metric Hollow Block	19,707 Pieces	1,576.524 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	25MMBB	25 mm Metric BB	143 Pieces	11.450 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	25MMBN	25 mm Metric Block BN	402 Pieces	32.160 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	25MMH	25 mm Metric Half Block	876 Pieces	35.040 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	25MMHBN	25 mm Metric Half BN	387 Pieces	15.480 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	25MMHH	25 mm Metric Halfhigh	233 Pieces	9.320 m <sup>2</sup>	125.0 Pieces/Day	
	CMU	25MMKO	25 mm Metric KO	1,956 Pieces	156.501 m <sup>2</sup>	125.0 Pieces/Day	
	CON	NEO3/8"X3	Neoprene 3/8"x3"	351 m	350.531 m	0.0 m/Day	

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
CON	RUBCJ+	Rubber Control Joint "+"	1,474 m	1,474.300 m	0.0 m/Day	
DRI	SSDR1/2X3	Stain. Drip Edge 1/2"x3"	147 m	146.666 m	0.0 m/Day	
DRI	SSTERM	Stainless Term. Bar	147 m	146.666 m	0.0 m/Day	
FLA	WRGRACE1	W.R. Grace 18" Flashing	132 m	132.169 m	91.4 m/Day	
FLA	WRGRACE2	W.R. Grace 20" Flashing	368 m	368.225 m	91.4 m/Day	
GRC	2500PSICY	2500 PSI Grout in Cu.Yrds	706 m <sup>3</sup>	706.085 m <sup>3</sup>	7.6 m <sup>3</sup> /Day	
INR	BLUE4"	Roxul Insulation 100 MM	1,320 m <sup>2</sup>	1,319.531 m <sup>2</sup>	111.5 m <sup>2</sup> /Day	
MN	MN1	Mortar Net 1"x10"	500 m	500.394 m	0.0 m/Day	
MOR	[B] Type S Port/Lime	1:1/2:4-1/2 Mix	565 m <sup>3</sup>	564.630 m <sup>3</sup>	0.0 m <sup>3</sup> /Day	
MOR	[H] Type S Port/Lime/Col	1:1/2:4-1/2 Mix	61 m <sup>3</sup>	61.499 m <sup>3</sup>	0.0 m <sup>3</sup> /Day	
REB	#5	15MM Rebar /Give Vert. Ht	27,469 m	27,469.438 m	0.0 m/Day	
REB	#5BB REBA	15MM Bond Beam Rebar	14,057 m	14,056.504 m	0.0 m/Day	
REB	#6	20MM Rebar /Give Vert. Ht	3,745 m	3,745.230 m	0.0 m/Day	
SCA	SCAFFOLDE	Exterior Scaffolding	1,745 m <sup>2</sup>	1,745.494 m <sup>2</sup>	92.9 m <sup>2</sup> /Day	
SCA	SCAFFOLDI	Interior Scaffolding	20,360 m <sup>2</sup>	20,360.328 m <sup>2</sup>	92.9 m <sup>2</sup> /Day	
WEE	WEEPVENT	Weep Vent	828 Each	828.281 Ea	0.0 Each/Day	
WIR	HDL31608"	HDG/Ladder 3/16"x 9 -8"	7,681 m	7,680.647 m	0.0 m/Day	
WIR	HDL31668"	HDG/Ladd 3/16"x 3/16" -8"	1,554 m	1,554.139 m	0.0 m/Day	
WIR	HDL9GA04"	Hot-Dipp./Ladder 9ga-10MM	4,377 m	4,377.115 m	0.0 m/Day	
WIR	HDL9GA06"	Hot-Dipp./Ladder 9ga-15MM	113 m	112.834 m	0.0 m/Day	
WIR	HDL9GA08"	Hot-Dipp./Ladder 9ga-20MM	34,271 m	34,271.397 m	0.0 m/Day	
WIR	HDL9GA10"	Hot-Dipp./Ladder 9ga-25MM	10,307 m	10,306.858 m	0.0 m/Day	

























