

Water Treatment Facility Prevailing Wage

Quantity/Bid - Totals Only

Class	Mat. ID	Material Description	Amount	Units	Quantity	Lay-Rate		----- Labor -----		----- Material -----		Man Days
						Waste	Units/Day	Per Unit	Ext. Cost	Per Unit	Ext. Cost	
0GC	DUMPSTERS	Dumpster Masonry Disposal	2	Ea	2 Each		0	\$0.00	\$0	\$600.00	\$1,200	0.0
ANC	POS12.5V4	HB-213 Wall Tie, Hook/Scr	368	Ea	368 Each		300	\$2.02	\$743	\$1.21	\$445	1.2
ANC	POS12.5VT	HB-213 Wall Tie, Hook/Tap	1,346	Ea	1,346 Each		300	\$2.02	\$2,717	\$1.49	\$2,005	4.5
ANC	PTA420	Partition Top Anchor 420	20	Ea	20 Each		75	\$8.08	\$162	\$4.00	\$80	0.3
ANC	REBARPO12	Rebar Positioner 12" CMU	696	Ea	696 Each		0	\$0.00	\$0	\$0.50	\$348	0.0
ANC	REBARPO8	Rebar Positioner 8" CMU	614	Ea	614 Each		0	\$0.00	\$0	\$0.48	\$295	0.0
ANC	STONEANCH	S.S. Stone Anchors	24	Ea	24 Each		0	\$0.00	\$0	\$4.00	\$96	0.0
BRI	MINF	Modular Brick Infill	15	SF	103 Pieces	4.00%	300	\$5.31	\$526	\$1.00	\$103	0.3
BRI	MTOOTH	Modular Brick Tooth	8	SF	56 Pieces	4.00%	150	\$10.63	\$574	\$1.00	\$56	0.4
CMU	HW08	8" NW CMU	1,971	SF	2,262 Pieces	2.00%	120	\$14.20	\$31,475	\$2.09	\$4,727	18.5
CMU	HW08BB	8" NW CMU-B.B.	39	SF	45 Pieces	2.00%	120	\$14.20	\$621	\$2.44	\$109	0.4
CMU	HW08BBL	8" NW CMU-B.B. Lintel	23	SF	27 Pieces	2.00%	120	\$14.20	\$369	\$2.44	\$65	0.2
CMU	HW08BN	8" NW CMU-BN	46	SF	53 Pieces	2.00%	120	\$14.20	\$738	\$2.44	\$129	0.4
CMU	HW08H	8" NW CMU Half	74	SF	169 Pieces	2.00%	120	\$14.20	\$2,356	\$1.56	\$264	1.4
CMU	HW08HBN	8" NW CMU Half BN	40	SF	93 Pieces	2.00%	120	\$14.20	\$1,292	\$1.86	\$173	0.8
CMU	HW08HI	8" NW CMU Half Infill	4	SF	9 Pieces	2.00%	80	\$19.93	\$179	\$1.56	\$14	0.1
CMU	HW08I	8" NW CMU Infill	19	SF	21 Pieces	2.00%	80	\$19.93	\$418	\$2.09	\$45	0.3
CMU	HW08KO	8" NW CMU-K.O.	156	SF	179 Pieces	2.00%	120	\$14.20	\$2,495	\$2.39	\$429	1.5
CMU	HW12	12" NW CMU	1,730	SF	1,985 Pieces	2.00%	115	\$14.81	\$28,832	\$3.05	\$6,055	16.9
CMU	HW12BB	12" NW CMU-B.B.	50	SF	58 Pieces	2.00%	115	\$14.81	\$841	\$3.40	\$197	0.5
CMU	HW12BN	12" NW CMU BN	4	SF	4 Pieces	2.00%	115	\$14.81	\$59	\$3.40	\$14	0.0
CMU	HW12DBN	12" NW CMU DBN	91	SF	104 Pieces	2.00%	115	\$14.81	\$1,511	\$3.40	\$354	0.9
CMU	HW12H	12" NW CMU Half	35	SF	80 Pieces	2.00%	115	\$14.81	\$1,155	\$2.29	\$182	0.7
CMU	HW12HBN	12" NW CMU Half BN	5	SF	12 Pieces	2.00%	115	\$14.81	\$178	\$2.64	\$32	0.1
CMU	HW12HDBN	12" NW CMU Half DBN	40	SF	91 Pieces	2.00%	115	\$14.81	\$1,318	\$2.64	\$240	0.8
CMU	HW12KO	12" NW CMU-K.O.	352	SF	404 Pieces	2.00%	115	\$14.81	\$5,862	\$3.35	\$1,352	3.4
CON	NEO3/8"X3	Neoprene 3/8"x3"	111	LF	111 LinFt		0	\$0.00	\$0	\$0.39	\$43	0.0
CON	RUBCJ+	Rubber Control Joint "+"	159	LF	159 LinFt		0	\$0.00	\$0	\$1.25	\$199	0.0
DRI	SSDR1/2X3	Stainless Drip Edge	309	LF	309 LinFt		0	\$0.00	\$0	\$1.40	\$433	0.0
DRI	TERMBAR	Termination Bar	309	LF	309 LinFt		0	\$0.00	\$0	\$1.90	\$587	0.0
FLA	YOMF5OZ20	York Multiflash 20" Wide	220	LF	220 LinFt		300	\$2.02	\$444	\$4.25	\$934	0.7
FLA	YOMF5OZ24	York Multiflash 24" Wide	89	LF	89 LinFt		300	\$2.02	\$180	\$5.10	\$456	0.3
GRC	2500PSICY	2500 PSI Grout in Cu.Yrds	37	CY	37 CbcYds		10	\$159.41	\$5,886	\$159.03	\$5,871	3.7
INR	THERMAX2"	Thermax Insul. 2" BY GC	3,062	SF	3,062 SqFt		0	\$0.00	\$0	\$0.00	\$0	0.0
MN	MN2	Mortar Trap 2"x10"	309	LF	309 LinFt		0	\$0.00	\$0	\$1.65	\$510	0.0
MOR	[B] Mortar For	CMU	492	CF	492 CbcFt		0	\$0.00	\$0	\$7.76	\$3,818	0.0
MOR	[G] Mortar For	Architectural CMU	270	CF	270 CbcFt		0	\$0.00	\$0	\$11.66	\$3,149	0.0
MOR	[H] Mortar For	Brick	4	CF	4 CbcFt		0	\$0.00	\$0	\$9.81	\$36	0.0
PRL	PCSILL63	Precast Sill 6"x3"	47	LF	47 LinFt		30	\$52.74	\$2,461	\$17.14	\$800	1.6
REB	#5	#5 Rebar / Give Vert. Ht	1,548	LF	1,548 LinFt		0	\$0.00	\$0	\$0.00	\$0	0.0
REB	#5BB REBA	#5 Bond Beam Rebar - 240"	492	LF	492 LinFt		0	\$0.00	\$0	\$0.00	\$0	0.0
REB	#6	#6 Rebar / Give Vert. Ht	2,175	LF	2,175 LinFt		0	\$0.00	\$0	\$0.00	\$0	0.0
REB	#6BB REBA	#6 Bond Beam Rebar - 240"	1,546	LF	1,546 LinFt		0	\$0.00	\$0	\$0.00	\$0	0.0
REV	GRHPLOC	Grout Heat Pump Location	2	Ea	2 Each		2	\$797.07	\$1,594	\$100.00	\$200	1.0
SCA	SCAFFOLDE	Exterior Scaffolding	4,207	SF	4,207 SqFt		0	\$0.00	\$0	\$0.00	\$0	0.0
SCA	SCAFFOLDI	Interior Scaffolding	5,459	SF	5,459 SqFt		0	\$0.00	\$0	\$0.00	\$0	0.0
SPL	SF04	4" Split Face	2,492	SF	2,860 Pieces	2.00%	125	\$12.66	\$35,494	\$3.86	\$11,040	22.4
SPL	SF04CN	4" Split Face L Corner	128	SF	147 Pieces	2.00%	125	\$12.66	\$1,823	\$6.40	\$940	1.2
SPL	SF04CNH	4" Split Face L Corner	23	SF	53 Pieces	2.00%	125	\$12.66	\$658	\$6.40	\$339	0.4
SPL	SF04H	4" Split Face Half	68	SF	155 Pieces	2.00%	125	\$12.66	\$1,924	\$2.90	\$450	1.2
SPL	SM04	4" Smooth Face	301	SF	345 Pieces	2.00%	125	\$12.66	\$4,281	\$3.21	\$1,107	2.7
SPL	SM04CN	4" Smooth Face L Corner	9	SF	10 Pieces	2.00%	125	\$12.66	\$127	\$6.40	\$65	0.1
SPL	SM04H	4" Smooth Face Half	18	SF	41 Pieces	2.00%	125	\$12.66	\$506	\$2.40	\$98	0.3
WEE	WEEPVENT	Weep Vent	115	Ea	115 Each		0	\$0.00	\$0	\$0.42	\$48	0.0
WIR	HDL9GA08"	Hot-Dipp./Ladder 9ga-- 8"	1,778	LF	1,778 LinFt		0	\$0.00	\$0	\$0.34	\$605	0.0
WIR	HDL9GA12"	Hot-Dipp./Ladder 9ga--12"	1,840	LF	1,840 LinFt		0	\$0.00	\$0	\$0.38	\$699	0.0

Water Treatment Facility Prevailing Wage

Quantity/Bid - Totals Only

Class	Mat. ID	Material Description	Amount	Units	Quantity	Lay-Rate Waste Units/Day	----- Labor ----- Per Unit	----- Material ----- Per Unit	----- Ext. Cost	----- Ext. Cost	Man Days
							Totals:		\$139,801	\$51,435	89.1

Water Treatment Facility Prevailing Wage

Quantity/Bid - Totals Only

Crew Section

Ratio of Production Masons to

ID	Description	Production Masons	Prod-Mason Days	Crew Days	Cost Per Day Whole Crew	Cost Per Day Per Prod-Mason	Extended Labor Cost	Ratio of Production Masons to			
								Super	Layout	Saw	Tender/Other
1	Brick Crew- 1-NWBF,5-B,3-L,1-O And Lull	5.00	29.9	5.975	\$7,911.62	\$1,582.32	\$47,274.39	5.00			1.25
2	Block Crew- 1-NWBF,5-B,4-L,1-O And Lull	5.00	46.4	9.287	\$8,517.38	\$1,703.48	\$79,103.51	5.00			1.00
4	Grout Crew- 1/8-BF,1-B,1-L	1.00	3.7	3.680	\$1,594.13	\$1,594.13	\$5,866.16	8.00			1.00
5	Ties, Insulation, Flashing- 1-Laborer	1.00	7.0	7.009	\$605.76	\$605.76	\$4,245.66				
7	Restoration Crew- 1/8-BF,1-B,1-L	1.00	2.1	2.077	\$1,594.13	\$1,594.13	\$3,311.50	8.00			1.00
Lay Crew Totals			89.1	28.029			\$139,801.22				
3	Washdown Crew- 1-Laborer	1.00	3.1	3.134	\$605.76	\$605.76	\$1,898.74				
All Crew Totals			92.2	31.163			\$141,699.96				

Totals by Labor ID

ID	Estimated					
	Hours	Base	Fringe	Burden	Total	Cost / Hour
Brick Non Forem	127.86	\$9,416.49	\$2,194.30	\$3,191.25	\$14,802.04	\$115.77
Brick Non-Union	656.56	\$45,071.65	\$11,267.91	\$15,274.78	\$71,614.34	\$109.07
Forklif Non-Uni	122.10	\$7,734.36	\$1,933.59	\$2,621.17	\$12,289.12	\$100.65
Laborer Non-Uni	567.80	\$27,059.26	\$6,764.82	\$9,170.38	\$42,994.46	\$75.72
	1,474.32	\$89,281.76	\$22,160.62	\$30,257.59	\$141,699.96	\$96.11

Totals by Equipment ID

ID	Description	Cost	Days	Cost / Day
Grout Pump	Grout Pump	\$735.97	3.680	\$200.00
Lull 1044	Lull 1044	\$2,289.39	15.263	\$150.00
Equipment Totals		\$3,025.36	18.942	

Water Treatment Facility Prevailing Wage

Quantity/Bid - Totals Only

		Costs & Taxes	Overhead	Profit	OH + Profit	Totals	% of Bid
Material Costs		\$51,435.20					
Misc. Taxable Costs		\$0.00					
Taxable Sub-Total		\$51,435.20					
	Tax 0.000%	\$0.00	7.00%	10.00%			
Material + Misc. Taxable Costs + Tax		\$51,435.20	\$3,600.46	\$5,503.57	\$9,104.03	\$60,539.23	23.9%
Base	63.008%	\$89,281.76					
Fringe	15.639%	\$22,160.62					
Burden	21.353%	\$30,257.59	7.00%	10.00%			
Crew Labor Cost		\$141,699.96	\$9,919.00	\$15,161.90	\$25,080.89	\$166,780.85	65.7%
Subbed Out			7.00%	10.00%			
Cleaning Cost		\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	
Equipment		\$3,025.36	\$211.78	\$323.71	\$535.49	\$3,560.85	1.4%
Mobilization		\$0.00					
Mockup Panel		\$1,500.00					
Misc. Accessori		\$2,000.00					
Move Lull		\$800.00					
		\$0.00					
Scaffold/Hoisti		\$15,200.00	7.00%	10.00%			
Misc. Sub-Total		\$19,500.00	\$1,365.00	\$2,086.50	\$3,451.50	\$22,951.50	9.0%
			7.00%	10.70%	17.70%		
Grand Totals		\$215,660.52	\$15,096.24	\$23,075.68	\$38,171.91	\$253,832.43	
			Without Misc. or OH&P	With Misc. and OH&P	Total Square Feet		
Average Cost Per Square Foot			\$25.24	\$32.66	7,771.50		

Water Treatment Facility Prevailing Wage

Report Run
1/22/2021 3:36 PM

Labor in Project

Page 1

Description	Rate	Amount	OverTime
Brick Non Forem			Bricklayer Foreman Prevailing Wage
Wages	Base	\$68.65	<input checked="" type="checkbox"/>
	Foreman Pay	\$5.00	<input type="checkbox"/>
Fringe	Benefits	\$17.16	<input checked="" type="checkbox"/>
Burden	Social Security	7.65% \$5.63	<input checked="" type="checkbox"/>
	Workmen's Compensation	16.00% \$11.78	<input type="checkbox"/>
	Federal Unemployment Ins.	0.80% \$0.59	<input checked="" type="checkbox"/>
	State Unemployment Ins.	7.75% \$5.71	<input checked="" type="checkbox"/>
	Liability Insurance	1.65% \$1.22	<input checked="" type="checkbox"/>
	Health Insurance	0.04% \$0.03	<input type="checkbox"/>
Brick Non-Union			Bricklayer Prevailing Wage
Wages	Base	\$68.65	<input checked="" type="checkbox"/>
Fringe	Benefits	\$17.16	<input checked="" type="checkbox"/>
Burden	Social Security	7.65% \$5.25	<input checked="" type="checkbox"/>
	Workmen's Compensation	16.00% \$10.98	<input type="checkbox"/>
	Federal Unemployment Ins.	0.80% \$0.55	<input checked="" type="checkbox"/>
	State Unemployment Ins.	7.75% \$5.32	<input checked="" type="checkbox"/>
	Liability Insurance	1.65% \$1.13	<input checked="" type="checkbox"/>
	Health Insurance	0.04% \$0.03	<input type="checkbox"/>
Forklif Non-Uni			Forklift Driver Prevailing Wage
Wages	Base	\$63.34	<input checked="" type="checkbox"/>
Fringe	Benefits	\$15.84	<input type="checkbox"/>
Burden	Social Security	7.65% \$4.85	<input checked="" type="checkbox"/>
	Workmen's Compensation	16.00% \$10.14	<input type="checkbox"/>
	Federal Unemployment Ins.	0.80% \$0.51	<input checked="" type="checkbox"/>
	State Unemployment Ins.	7.75% \$4.91	<input checked="" type="checkbox"/>
	Liability Insurance	1.65% \$1.05	<input checked="" type="checkbox"/>
	Health Insurance	0.04% \$0.03	<input type="checkbox"/>
Laborer Non-Uni			Laborer Prevailing Wage
Wages	Base	\$47.66	<input checked="" type="checkbox"/>
Fringe	Benefits	\$11.91	<input type="checkbox"/>
Burden	Social Security	7.65% \$3.65	<input checked="" type="checkbox"/>
	Workmen's Compensation	16.00% \$7.62	<input type="checkbox"/>
	Federal Unemployment Ins.	0.80% \$0.38	<input checked="" type="checkbox"/>
	State Unemployment Ins.	7.75% \$3.69	<input checked="" type="checkbox"/>
	Liability Insurance	1.65% \$0.79	<input checked="" type="checkbox"/>
	Health Insurance	0.04% \$0.02	<input type="checkbox"/>

Water Treatment Facility Prevailing Wage

Report Run
1/22/2021

3:36 PM

Crews in Project

Page 1

Crew 1 Brick Crew- 1-NWBF,5-B,3-L,1-O And Lull

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Brick Non Forem	Bricklayer Foreman Prevailing Wage	Supervisor	1.00	8.00			\$926.15
Brick Non-Union	Bricklayer Prevailing Wage	Production	5.00	8.00			\$4,362.99
Forklif Non-Uni	Forklift Driver Prevailing Wage	Tender/Other	1.00	8.00			\$805.18
Laborer Non-Uni	Laborer Prevailing Wage	Tender/Other	3.00	8.00			\$1,817.29
Lull 1044	Lull 1044	Equipment	1.00				\$150.00

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$4,985.60	\$1,236.40	\$1,689.62	\$150.00	\$8,061.62
Cost per Prod.Man Day	\$997.12	\$247.28	\$337.92	\$30.00	\$1,612.32

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
	8.00			40.00	32.00

Production Masons 5.00 Checked if, the number of Production Masons was Overridden

Crew 2 Block Crew- 1-NWBF,5-B,4-L,1-O And Lull

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Brick Non Forem	Bricklayer Foreman Prevailing Wage	Supervisor	1.00	8.00			\$926.15
Brick Non-Union	Bricklayer Prevailing Wage	Production	5.00	8.00			\$4,362.99
Forklif Non-Uni	Forklift Driver Prevailing Wage	Tender/Other	1.00	8.00			\$805.18
Laborer Non-Uni	Laborer Prevailing Wage	Tender/Other	4.00	8.00			\$2,423.06
Lull 1044	Lull 1044	Equipment	1.00				\$150.00

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$5,366.85	\$1,331.71	\$1,818.82	\$150.00	\$8,667.38
Cost per Prod.Man Day	\$1,073.37	\$266.34	\$363.76	\$30.00	\$1,733.48

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
	8.00			40.00	40.00

Production Masons 5.00 Checked if, the number of Production Masons was Overridden

Crew 3 Washdown Crew- 1-Laborer

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Laborer Non-Uni	Laborer Prevailing Wage	Production	1.00	8.00			\$605.76

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$381.25	\$95.31	\$129.20		\$605.76
Cost per Prod.Man Day	\$381.25	\$95.31	\$129.20		\$605.76

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
				8.00	

Production Masons 1.00 Checked if, the number of Production Masons was Overridden

Water Treatment Facility Prevailing Wage

Report Run
1/22/2021

3:36 PM

Crews in Project

Page 2

Crew 4 Grout Crew- 1/8-BF,1-B,1-L

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Brick Non Forem	Bricklayer Foreman Prevailing Wage	Supervisor	1.00	1.00			\$115.77
Brick Non-Union	Bricklayer Prevailing Wage	Production	1.00	8.00			\$872.60
Laborer Non-Uni	Laborer Prevailing Wage	Tender/Other	1.00	8.00			\$605.76
Grout Pump	Grout Pump	Equipment	1.00				\$200.00

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$1,004.08	\$249.77	\$340.28	\$200.00	\$1,794.13
Cost per Prod.Man Day	\$1,004.08	\$249.77	\$340.28	\$200.00	\$1,794.13

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
	1.00			8.00	8.00

Production Masons 1.00 Checked if, the number of Production Masons was Overridden

Crew 5 Ties, Insulation, Flashing- 1-Laborer

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Laborer Non-Uni	Laborer Prevailing Wage	Production	1.00	8.00			\$605.76

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$381.25	\$95.31	\$129.20		\$605.76
Cost per Prod.Man Day	\$381.25	\$95.31	\$129.20		\$605.76

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
				8.00	

Production Masons 1.00 Checked if, the number of Production Masons was Overridden

Crew 6 Precast Crew-1/8-BF,2-B,1-L,1-O And Lull

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Brick Non Forem	Bricklayer Foreman Prevailing Wage	Supervisor	1.00	1.00			\$115.77
Brick Non-Union	Bricklayer Prevailing Wage	Production	2.00	8.00			\$1,745.20
Forklif Non-Uni	Forklift Driver Prevailing Wage	Tender/Other	1.00	8.00			\$805.18
Laborer Non-Uni	Laborer Prevailing Wage	Tender/Other	1.00	8.00			\$605.76
Lull 1044	Lull 1044	Equipment	1.00				\$150.00

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$2,060.02	\$513.75	\$698.14	\$150.00	\$3,421.91
Cost per Prod.Man Day	\$1,030.01	\$256.88	\$349.07	\$75.00	\$1,710.95

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
	1.00			16.00	16.00

Production Masons 2.00 Checked if, the number of Production Masons was Overridden

Water Treatment Facility Prevailing Wage

Report Run
1/22/2021

3:36 PM

Crews in Project

Page 3

Crew 7 Restoration Crew- 1/8-BF,1-B,1-L

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Brick Non Forem	Bricklayer Foreman Prevailing Wage	Supervisor	1.00	1.00			\$115.77
Brick Non-Union	Bricklayer Prevailing Wage	Production	1.00	8.00			\$872.60
Laborer Non-Uni	Laborer Prevailing Wage	Tender/Other	1.00	8.00			\$605.76

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$1,004.08	\$249.77	\$340.28		\$1,594.13
Cost per Prod.Man Day	\$1,004.08	\$249.77	\$340.28		\$1,594.13

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
	1.00			8.00	8.00

Production Masons 1.00 Checked if, the number of Production Masons was Overridden

Crew 8 Scaffolding Crew- 2-L,1-O & 1 Lull

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Laborer Non-Uni	Laborer Prevailing Wage	Production	2.00	8.00			\$1,211.53
Forklif Non-Uni	Forklift Driver Prevailing Wage	Tender/Other	1.00	8.00			\$805.18
Lull 1044	Lull 1044	Equipment	1.00				\$150.00

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$1,269.25	\$317.31	\$430.15	\$150.00	\$2,166.71
Cost per Prod.Man Day	\$634.62	\$158.66	\$215.07	\$75.00	\$1,083.35

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
				16.00	8.00

Production Masons 2.00 Checked if, the number of Production Masons was Overridden

Crew 9 Demolition Crew- 2-L

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Laborer Non-Uni	Laborer Prevailing Wage	Production	2.00	8.00			\$1,211.53

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$762.50	\$190.62	\$258.41		\$1,211.53
Cost per Prod.Man Day	\$381.25	\$95.31	\$129.20		\$605.76

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
				16.00	

Production Masons 2.00 Checked if, the number of Production Masons was Overridden

Water Treatment Facility Prevailing Wage

Report Run
1/22/2021

3:36 PM

Crews in Project

Page 4

Crew A Mobilization Crew- 2-L

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Laborer Non-Uni	Laborer Prevailing Wage	Production	2.00	8.00			\$1,211.53

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$762.50	\$190.62	\$258.41		\$1,211.53
Cost per Prod.Man Day	\$381.25	\$95.31	\$129.20		\$605.76

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
				16.00	

Production Masons 2.00 Checked if, the number of Production Masons was Overridden


Crew B Air Vapor Barrier Crew- 2-L

ID	Description	Category	Qty	- Hours per Day -			Cost per Day
				Reg	x1.5	x2	
Laborer Non-Uni	Laborer Prevailing Wage	Production	2.00	8.00			\$1,211.53

	Base	Fringe	Burden	Equipment	Total
Cost per Crew Day	\$762.50	\$190.62	\$258.41		\$1,211.53
Cost per Prod.Man Day	\$381.25	\$95.31	\$129.20		\$605.76

Man Hours per Crew Day	Supervisor	Layout	Sawman	Production	Tender / Other
				16.00	

Production Masons 2.00 Checked if, the number of Production Masons was Overridden



WEST DISTRICT
FROM THE PLANT
PROJECT 3
SCHEDULES
AND SPECIFICATIONS


FIRST FLOOR
SCALE 3/16" = 1'-0"

HEAT PUMPS
MECHANICAL
GROUT CMU
ANCHOR
TYP.

MATCH
3'-0" X 3'-0"

ACTIVE





REVISIONS:
1. REVISED TO SHOW THE
LOCATION OF THE AERATION TOWER
AND THE STORAGE AREA.



EMERGENCY
EYEWASH
SHOWER

CONCRETE SLAB
FOUNDATION, SEE
STRUCTURAL
DRAWING

AERATION
TOWER



PIERCE

light-pierce.com

